Chrisbeth Integrated CONCEPT LTD
RC: 672619 | TIN NO: 15227158-0001

No. 8 Chief Gilbert Nworlu Avenue
Rumuokoro, Port Harcourt,
Rivers State, Nigeria.

Tel: +234 916 317 9301

RC NO: 672619
TIN NO: 15227158-0001

PROCUREMENT OFFICER
DAEWOO E&C NIGERIA LIMITED
MR. AGBARA PRINCE

QUOTATION

Quote # Quote-CICL-0026/1016-06/1016-07/1016-08/1016-09/1016-10/1016-11/1016-12
Quote Date: 20/10/2026
MR Number: OPCH1-KP001D/KP002D/KP003D/KP004D/KP005D/KP006D/KP007D
Item Description: Piping Materials

S/N	MR	ITEM	TOTAL AMOUNT	MAKER	REMARK
1	KP001D	PIPE FITTING	$ 120,205.78	See the offer detail	Based on Non-TAMAP vendor for coating and painting vendor.
2	KP002D	GRV PIPE	$ 227,346.53	Sarplast s.r.l. (ITALY)	Please refer to "Additional Scope of Supply " at the bottom. : Site lamination for erection, including 30% spare :
3	KP003D	HDPE PIPE & FITTINGS	$ 21,439.70	COSMO I&D IND (KOREA)	Based on Non -TAMAP vendor * Fusion training for HDPE pipes is available by visiting the manufacturer's factory and the certificate
4	KP004D	VALVE	$ 16,169.48	NEWAY (CHINA)	Regarding no.3 BUTTERFLY V/V , we can provide based on the manufacture's standard and "handle length 1950 * 2ea,1650 * 1ea is not available.
5	KP005D	FLANGE	$ 4,686.08	Shanxi Guanjiaying(CHINA), Samho fitting (korea)	
6	KP006D	GASKET	$ 1,123.42	TEADIT (INDIA)	
7	KP007D	STUD BOLT & NUT	$ 3,250.40	SBN Industries (Malaysia)	
		GRAND TOTAL	**$ 394,221.39**		

TERMS	
CURRENCY	USD
PROJECT	NIGERIA HI OPF BLOCK PJ
MAKER	Please see the details.
DELIVERY TIME:	Please see the details.
DELIVERY TERMS	Please see the details.
PAYMENT TERMS	T.T (30% in advance / 60% after delivery / 10% approval of Final as-built drawing)
ORIGIN	Please see the details.
INSPECTION	Material inspection prior to shipment shall be final, but 3rd party inspection is acceptable at buyer's care and cost.
PACKING	All packings shall be strictly in accordance to mill and warehouse standard and norm.
VALIDITY	14day after issue

RC NO: 672619
TIN NO: 15227158-0001

PROCUREMENT OFFICER
DAEWOO E&C NIGERIA LIMITED
MR. AGBARA PRINCE

QUOTATION

Quote # Quote-CICL-0026/1016-06
Quote Date: 20/10/2026
MR Number: OPCH1-KP001D
Item Description: CS Pipe & Fittings

S/N	ITEMS	DESCRIPTION	END	SIZE	SCH	LENGTH	UNIT	QTY	UNIT PRICE ($)	AMOUNT ($)	MAKER
1	CS seamless pipe	ASTM A106 GR B Ext PAINTING, internal - N/A	BE	24"	S20	6M or DRL	M	6	$ 1,018.44	$ 6,110.64	PIPE : NSC, V&M,JFE, TENARIS,TPCO Painting : GUNIL STEEL, DOWON,HANJONG (KOREA)
2	CS seamless pipe	ASTM A106 GR B Ext PAINTING, internal - N/A	BE	6"	S40	6M	M	828	$ 110.44	$ 91,444.32	PIPE : NSC, V&M,JFE, TENARIS,BAOSTEEL, TPCO Painting : GUNIL STEEL, DOWON,HANJONG (KOREA)
3	CS seamless pipe	ASTM A106 GR B Ext- 3LPE, internal - N/A	BE	6"	S40	6M	M	48	$ 104.55	$ 5,018.40	PIPE : NSC, V&M,JFE, TENARIS,BAOSTEEL, TPCO Coating : GUNIL STEEL, DOWON,HANJONG (KOREA)
4	CS seamless pipe	ASTM A106 GR B Ext PAINTING, internal - N/A	BE	4"	S40	6M	M	12	$ 65.74	$ 788.88	PIPE : NSC, V&M,JFE, TENARIS,BAOSTEEL, TPCO Painting : GUNIL STEEL, DOWON,HANJONG (KOREA)
5	CS seamless pipe	ASTM A106 GR B Ext PAINTING, internal - N/A	BE	2"	S80	6M	M	12	$ 38.13	$ 457.56	PIPE : NSC, V&M,JFE, TENARIS,BAOSTEEL, TPCO Painting : GUNIL STEEL, DOWON,HANJONG (KOREA)
6	90 Elbow	ASTM A234 WPB Ext PAINTING, internal - N/A	BE	6"	S40		EA	27	$ 114.92	$ 3,102.84	Fitting : TK BEND, SUNGKWANG BEND Painting : GUNIL STEEL, DOWON,HANJONG (KOREA)
7	90 Elbow	ASTM A234 WPB Ext- 3LPE, internal - N/A	BE	6"	S40		EA	3	$ 113.78	$ 341.34	Fitting : TK BEND, SUNGKWANG BEND Coating : GUNIL STEEL, DOWON,HANJONG (KOREA)
8	90 Elbow	ASTM A234 WPB Ext PAINTING, internal - N/A	BE	2"	S80		EA	2	$ 29.35	$ 58.70	Fitting : TK BEND, SUNGKWANG BEND Painting : GUNIL STEEL, DOWON,HANJONG (KOREA)
9	Tee	ASTM A234 WPB Ext PAINTING, internal - N/A	BE	2"	S80		EA	2	$ 41.55	$ 83.10	Fitting : TK BEND, SUNGKWANG BEND Painting : GUNIL STEEL, DOWON,HANJONG (KOREA)
10	Packing						LOT	1	$ 12,800.00	$ 12,800.00	
									TOTAL AMOUNT ($)	**$ 120,205.78**	


Chrisbeth Integrated
CONCEPT LTD
RC: 672619 | TIN NO: 15227158-0001

No. 8 Chief Gilbert Nworlu Avenue
Rumuokoro, Port Harcourt,
Rivers State, Nigeria.

Tel: +234 916 317 9301

NOTES
Material spec : Acc to ASTM A106 , A234 (No guarantee for additional requirements beyond ASTM standard conditions) Coating: 3LPE in accordance with DIN 30670 (PE powder fusion applied , Color: RED) Painting: Total DFT min. 300 microns, Color: Light Grey (RAL 7004) - Surface preparation: SSPC-SP 10 - Primer: Zinc silicate primer, 60 microns - Intermediate coat: Epoxy - Top coat: Non-isocyanate or polyurethane Pipe ends: 200 mm from each end left uncoated (pipe only) No.1) Based on 6M/PCS. If supplied in DRL, price to be settled on actual delivered length at USD 795.66/m (max. 11.8 m/PC) Packing: Wooden skid bundle or wooden box. Plastic caps on pipe ends

TERMS	
CURRENCY	USD
PROJECT	NIGERIA HI OPF BLOCK PJ
DELIVERY TIME:	EXW 3 months after PO
DELIVERY TERMS	FOB Busan sea port
PAYMENT:	T.T (30% in advance / 60% after delivery / 10% approval of Final as-built drawing)



SIGNATURE
CHRISTIAN .E. A./Director

RC NO: 672619
TIN NO: 15227158-0001

PROCUREMENT OFFICER
DAEWOO E&C NIGERIA LIMITED
MR. AGBARA PRINCE

QUOTATION

Quote # Quote-CICL-0026/1016-07
Quote Date: 20/10/2026
MR Number: OPCH1-KP002D-01
Item Description: GRV pipe & fitting

S/N	ITEMS	Resin - Material liner/Mech./Gel coat	Specification	Joint/ drilling of flanges	UNIT	QTY	UNIT PRICE ($)	AMOUNT ($)
1	PIPE (GRV/STRAIGHT)	Epoxy Bisphenol 'A' Vinylester Resin	600 (24")	Plain ends	m	177	$ 312.81	$ 55,367.37
2	PIPE w/ Water Ring Puddle Flange, L=1.2m	Epoxy Bisphenol 'A' Vinylester Resin	600 (24")	Plain ends	pc	1	$ 1,672.00	$ 1,672.00
3	PIPE (GRV/STRAIGHT)	Epoxy Bisphenol 'A' Vinylester Resin	100 (4")	Plain ends	m	810	$ 60.48	$ 48,988.80
4	PIPE w/ Water Ring Puddle Flange, L=1.2m	Epoxy Bisphenol 'A' Vinylester Resin	100 (4")	Plain ends	pc	8	$ 436.01	$ 3,488.08
5	PIPE (GRV/STRAIGHT)	Epoxy Bisphenol 'A' Vinylester Resin	75 (3")	Plain ends	m	24	$ 56.64	$ 1,359.36
6	PIPE (GRV/STRAIGHT)	Epoxy Bisphenol 'A' Vinylester Resin	50 (2")	Plain ends	m	540	$ 53.29	$ 28,776.60
7	GRP ELBOW 45° R=1.5DN	Epoxy Bisphenol 'A' Vinylester Resin	100 (4")	Plain ends	pc	6	$ 73.28	$ 439.68
8	GRP ELBOW 45° R=1.5DN	Epoxy Bisphenol 'A' Vinylester Resin	75 (3")	Plain ends	pc	3	$ 56.81	$ 170.43
9	GRP ELBOW 45° R=1.5DN	Epoxy Bisphenol 'A' Vinylester Resin	50 (2")	Plain ends	pc	5	$ 40.64	$ 203.20
10	GRP ELBOW 90° R=1.5DN	Epoxy Bisphenol 'A' Vinylester Resin	600 (24")	Plain ends	pc	4	$ 2,320.81	$ 9,283.24
11	GRP ELBOW 90° R=1.5DN	Epoxy Bisphenol 'A' Vinylester Resin	100 (4")	Plain ends	pc	13	$ 133.61	$ 1,736.93
12	GRP ELBOW 90° R=1.5DN	Epoxy Bisphenol 'A' Vinylester Resin	75 (3")	Plain ends	pc	7	$ 103.36	$ 723.52
13	GRP ELBOW 90° R=1.5DN	Epoxy Bisphenol 'A' Vinylester Resin	50 (2")	Plain ends	pc	80	$ 74.09	$ 5,927.20
14	GRP CAP	Epoxy Bisphenol 'A' Vinylester Resin	100 (4")	Plain ends	pc	10	$ 138.88	$ 1,388.80
15	GRP STUB END + Galv. Steel Backing Ring ANSI#150	Epoxy Bisphenol 'A' Vinylester Resin	100 (4")	FF / Plain ends	pc	9	$ 222.25	$ 2,000.25
16	GRP STUB END + Galv. Steel Backing Ring ANSI#150	Epoxy Bisphenol 'A' Vinylester Resin	75 (3")	FF / Plain ends	pc	4	$ 165.12	$ 660.48
17	GRP STUB END + Galv. Steel Backing Ring ANSI#150	Epoxy Bisphenol 'A' Vinylester Resin	50 (2")	FF / Plain ends	pc	40	$ 142.40	$ 5,696.00
18	GRP TEE PIECE	Epoxy Bisphenol 'A' Vinylester Resin	100x100	Plain ends	pc	9	$ 259.69	$ 2,337.21
19	GRP TEE PIECE	Epoxy Bisphenol 'A' Vinylester Resin	100x75	Plain ends	pc	4	$ 225.60	$ 902.40
20	GRP TEE PIECE	Epoxy Bisphenol 'A' Vinylester Resin	100x50	Plain ends	pc	40	$ 199.85	$ 7,994.00
21 A	GRP FIXED FLANGES - ANSI#150	Epoxy Bisphenol 'A' Vinylester Resin	600	FF / Plain ends	pc	2	$ 1,698.20	$ 3,396.40
21 B	GRP BLIND FLANGES - ANSI#150	Epoxy Bisphenol 'A' Vinylester Resin	600	FF / Plain ends	pc	2	$ 3,062.48	$ 6,124.96
21 C	GRP BLIND FLANGES - ANSI#150	Epoxy Bisphenol 'A' Vinylester Resin	100	FF / Plain ends	pc	9	$ 349.29	$ 3,143.61
21 D	GRP BLIND FLANGES - ANSI#150	Epoxy Bisphenol 'A' Vinylester Resin	75	FF / Plain ends	pc	4	$ 239.31	$ 957.24
21 E	GRP BLIND FLANGES - ANSI#150	Epoxy Bisphenol 'A' Vinylester Resin	50	FF / Plain ends	pc	40	$ 183.24	$ 7,329.60
21 F	BOLTS & NUTS in Galvalized Steel + Gaskets	Galvanized Steel	600	Plain ends	pc	22	$ 617.63	$ 13,587.86
21 G	BOLTS & NUTS in Galvalized Steel + Gaskets	Galvanized Steel	100	Plain ends	pc	270	$ 24.88	$ 6,717.60
21 H	BOLTS & NUTS in Galvalized Steel + Gaskets	Galvanized Steel	75	Plain ends	pc	23	$ 24.27	$ 558.21
21 I	BOLTS & NUTS in Galvalized Steel + Gaskets	Galvanized Steel	50	Plain ends	pc	273	$ 23.50	$ 6,415.50
							TOTAL AMOUNT ($)	**$ 227,346.53**

Chrisbeth Integrated
CONCEPT LTD
RC: 672619 | TIN NO: 15227158-0001

No. 8 Chief Gilbert Nworlu Avenue
Rumuokoro, Port Harcourt,
Rivers State, Nigeria.

Tel: +234 916 317 9301

[Additional Scope] - Site lamination for erection, including 30% spare

Item Name	Specification	Unit	Q'ty	Unit	Amount	Remarks
Raw Materials for Site Lamination	DN600, Epoxy Bisphenol A Vinylester Resin, NP 16 bar	EA	24	$ 448.00	$ 10,752.00	Underground (UG), ISO 14692
Raw Materials for Site Lamination	DN100, Epoxy Bisphenol A Vinylester Resin, NP 16 bar	EA	270	$ 3.84	$ 1,036.80	Underground (UG), ISO 14692
Raw Materials for Site Lamination	DN75, Epoxy Bisphenol A Vinylester Resin, NP 16 bar	EA	23	$ 2.94	$ 67.62	Underground (UG), ISO 14692
Raw Materials for Site Lamination	DN50, Epoxy Bisphenol A Vinylester Resin, NP 16 bar	EA	273	$ 2.94	$ 802.62	Underground (UG), ISO 14692
	Engineering including isomertrics and Stress Analysis					Not included
	Factory test, Documentatino y and Standard packint					Included
					$ 12,659.04	

NOTES	
CURRENCY	USD
PROJECT	NIGERIA HI OPF BLOCK PJ
MAKER	Gruppo Sarplast s.r.l.
DESIGN	16 bar / 50°C, UG-ISO14692, Stiffness >5,000 N/m², Epoxy Bisphenol 'A' Vinylester Resin
DELIVERY TIME:	12 Weeks after PO
DELIVERY TERMS	Ex Works Factory of S.Luce (Pisa), Italy
PAYMENT:	T.T (30% in advance / 60% after delivery / 10% approval of Final as-built drawing)



SIGNATURE
CHRISTIAN .E. A./Director

RC NO: 672619
TIN NO: 15227158-0001

PROCUREMENT OFFICER
DAEWOO E&C NIGERIA LIMITED
MR. AGBARA PRINCE

QUOTATION

Quote # Quote-CICL-0026/1016-08
Quote Date: 20/10/2026
MR Number: OPCH1-KP003D
Item Description: HDPE Pipe & Fittings

S/N	ITEMS	SPECIFICATION	SIZE	UNIT	QTY	UNIT PRICE ($)	AMOUNT ($)	REMARK
1	PIPE (HDPE / ROLL)	2" x 100 meter Roll, HDPE, SCH DR11, PE4710 ASTM 3350 LL	63mm * 60M/RO	EA	24	$ 451.40	$ 10,833.60	PE100,SDR11 (total 1440m)
2	PIPE (HDPE / STRAIGHT)	2" x 11.8 meter, HDPE, SCH DR11, PE4710 ASTM 3350	63mm * 5.8M	PCS	108	$ 45.13	$ 4,874.04	PE100,SDR11 (total 626.4m)
3	PIPE (HDPE / STRAIGHT)	1.5" x 11.8 meter, HDPE, SCH DR11, PE4710 ASTM 3350	50mm * 5.8M	PCS	2	$ 28.54	$ 57.08	PE100,SDR11 (total 11.6m)
4	45° Elbow (HDPE)	2" HDPE, 45 DEG, SW, LR, SCH DR11, PE4710 ASTM 3350	63mm	EA	3	$ 27.38	$ 82.14	PE100,SDR11
5	90° Elbow (HDPE)	2" HDPE, 90 DEG, SW, LR, SCH DR11, PE4710 ASTM 3350	63mm	EA	28	$ 19.20	$ 537.60	PE100,SDR11
6	90° Elbow (HDPE)	1.5" HDPE, 90 DEG, SW, LR, SCH DR11, PE4710 ASTM 3350	50mm	EA	5	$ 13.75	$ 68.75	PE100,SDR11
7	CAP (HDPE)	2" HDPE, CAP, BW, SCH DR11, PE4710 ASTM 3350	63mm	EA	8	$ 13.75	$ 110.00	PE100,SDR11
8	REDUCER (HDPE)	2" x 1.5" HDPE, RED, CONC, SW, SCH DR11, PE4710 ASTM 3350	63mm*50mm	EA	5	$ 17.01	$ 85.05	PE100,SDR11
9	STUB END (HDPE)	2" HDPE, STUB END, PE, BW, SCH DR11, PE4710 ASTM 3350	63mm	EA	22	$ 53.22	$ 1,170.84	PE100,SDR11
10	STUB END (HDPE)	1.5" HDPE, STUB END, PE, BW, SCH DR11, PE4710 ASTM 3350	50mm	EA	6	$ 21.45	$ 128.70	PE100,SDR11
11	TEE (HDPE)	2" HDPE, EQUAL, PE, BW, SCH DR11, PE4710 ASTM 3350	63mm	EA	17	$ 24.70	$ 419.90	PE100,SDR11
12	HYDRO TEST KIT	63MM ADAPTER / PE 100, 63MM FF FLANGE / SS275, 63MM FF FLANGE - BLIND / SS275 (3/4" HOLE DRILLING), PRESSURE GAUGE AND OTHERS, M14 BOLT -NUT- WASHER / SS275		SET	2	$ 1,536.00	$ 3,072.00	HYDROSTATIC TESTER SOLD SEPARATELY
						TOTAL AMOUNT ($)	**$ 21,439.70**	


Chrisbeth Integrated
CONCEPT LTD
RC: 672619 | TIN NO: 15227158-0001

No. 8 Chief Gilbert Nworlu Avenue
Rumuokoro, Port Harcourt,
Rivers State, Nigeria.

Tel: +234 916 317 9301

NOTE
* Offer basis : - Metric size HDPE PE100, SDR11 (OD 63 mm / 50 mm) per ISO 4427, manufacturer's standard - Not PE4710 / ASTM D3350 / IPS size as per MR * Dimensions and properties : refer to the attached manufacturer's catalog (COSMOIND) - Pipe p.8 / 90° elbow p.12 / 45° elbow p.13 / Tee p.14 / Reducer p.16 / End cap p.17 / Stub end p.19 - Catalog dimensions are manufacturer's standard and subject to change for quality improvement * Pipe : straight pipe 5.8 m/PC, roll 60 m/ROLL (manufacturer's standard) * Marking : Acc to manufacturer standard * Packing : Wooden pallet * Stub end backing ring : excluded - Mating steel lap joint flanges are separately supplied under KP005D * Hydrostatic tester : sold separately (hydro test kit only included) * Fusion training : certificate issued at manufacturer's factory after training - Site dispatch is not available. Fusion machine is not included * To be confirmed before PO : 1) Mating steel lap joint flange bore (KP005D No.7,8,11,15) to be machined for 63 mm / 50 mm OD stub end neck 2) Stub end neck OD and collar OD (63 mm / 50 mm) vs. flange bolt circle clearance 3) Joint type (fitting) : SW or BW 4) 1.5" (50 mm) butt fusion stub end dimensions and availability

TERMS	
CURRENCY	USD
PROJECT	NIGERIA HI OPF BLOCK PJ
MAKER	COSMO I&D IND (KOREA)
DELIVERY TIME:	EXW 50 days after PO
DELIVERY TERMS	FOB BUSAN SEA PORT
PAYMENT:	T.T (30% in advance / 60% after delivery / 10% approval of Final as-built drawing)



SIGNATURE
CHRISTIAN .E. A./Director

RC NO: 672619
TIN NO: 15227158-0001

PROCUREMENT OFFICER
DAEWOO E&C NIGERIA LIMITED
MR. AGBARA PRINCE

QUOTATION

Quote # Quote-CICL-0026/1016-09
Quote Date: 20/10/2026
MR Number: OPCH1-KP004D
Item Description: VALVE (BASE)

S/N	ITEMS	SPECIFICATION	Design spec	Description	UNIT	QTY	UNIT PRICE ($)	AMOUNT ($)	REMARK
1	VALVE (BALL)	6" A105/A216 GR WCB/WCC, CL150#, RF, RP, LP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN150,CL150,FL,RB,CS,316/PTFE	EA	3	$ 1,612.80	$ 4,838.40	
2	VALVE (CHECK)	6" A105/A216 GR WCB/WCC, CL150#, RF, SWING, TRIM: AISI 316, STELLITE	BS 1868	VCHS,DN150,CL150,FL,CS,410/ST6	EA	2	$ 941.57	$ 1,883.14	
3	VALVE (BUTTERFLY)	4" A395 60-40-18, CONCENTRIC, LUG TYPE, DISC: ALUMINUM BRONZE, LINING: EPDM	API STD 609	VBUL,NPS 4,PN16,LUG,RF,DI,EPDM	EA	3	$ 465.41	$ 1,396.23	Regarding no.3 BUTTERFLY V/V , we can provide based on the manufacture's standard and "handle length 1950 * 2ea,1650 * 1ea is not available.
4	VALVE (BALL)	2" A105/A216 GR WCB/WCC, CL150#, RF, RP, LP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN50,CL150,FL,RB,CS,316/PTFE	EA	4	$ 321.02	$ 1,284.08	
5	VALVE (BALL)	2" A182-F316/A351-CF8M, CL150#, FF, RP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN50,CL150,FL,RB,316,316/PTFE	EA	2	$ 626.69	$ 1,253.38	
6	VALVE (BALL)	2" A182-F316/A351-CF8M, CL150#, FLOATING, FF, RP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN50,CL150,FL,RB,316,316/PTFE	EA	5	$ 626.69	$ 3,133.45	
7	VALVE (BALL)	1.5" A182-F316/A351-CF8M, CL150#, FLOATING, FF, RP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN40,CL150,FL,RB,316,316/PTFE	EA	5	$ 476.16	$ 2,380.80	
						TOTAL AMOUNT ($)		**$ 16,169.48**	


NOTE
1. Technical Any item not specified in this quotation shall be in accordance with Manufacturer's (Neway) standard practice. Painting: Manufacturer's standard coating system (Shell/MESC coating spec compliance to be confirmed). Pressure test: API 598 or API 6D. Visual inspection of castings: MSS-SP-55 / ASME B16.34. Marking: MSS-SP-25. NDE not included unless specifically listed in this quotation; available at additional cost if required by MESC SPE. **2. Inspection** Ex-works delivery upon completion of Seller's own in-house inspection. Third-party (source) inspection cost, if required by Purchaser, to be borne by Buyer. **3. Documentation** Documents included: MTC/Test Report per EN 10204 3.1, API 598/6D test certificates, GA Drawing, IOM Manual, Standard QC Plan. GA Drawing, Data Sheet & Calculation Sheet available after order confirmation only. Other documentation available upon request and may incur additional cost. **4. Packing method :** Export seaworthy wooden box.

Chrisbeth Integrated
CONCEPT LTD
RC: 672619 | TIN NO: 15227158-0001

No. 8 Chief Gilbert Nworlu Avenue
Rumuokoro, Port Harcourt,
Rivers State, Nigeria.

Tel: +234 916 317 9301

TERMS	
CURRENCY	USD
PROJECT	NIGERIA HI OPF BLOCK PJ
MAKER	NEWAY (CHINA), ZG VALVE (CHINA)
DELIVERY TIME:	EXW 20~24 weeks after PO
DELIVERY TERMS	FOB CHINA SEA PORT
PAYMENT:	T.T (30% in advance / 60% after delivery / 10% approval of Final as-built drawing)



SIGNATURE
CHRISTIAN .E. A./Director

RC NO: 672619
TIN NO: 15227158-0001

PROCUREMENT OFFICER
DAEWOO E&C NIGERIA LIMITED
MR. AGBARA PRINCE

QUOTATION


Quote # Quote-CICL-0026/1016-09
Quote Date: 20/10/2026
MR Number: OPCH1-KP004D
Item Description: VALVE (OPTIONAL)

S/N	ITEMS	SPECIFICATION	Design spec	Description	UNIT	QTY	UNIT PRICE ($)	AMOUNT ($)	REMARK
1	VALVE (BALL)	6" A105/A216 GR WCB/WCC, CL150#, RF, RP, LP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN150,CL150,FL,RB,CS,316/PTFE	EA	3	$ 1,612.80	$ 4,838.40	
2	VALVE (CHECK)	6" A105/A216 GR WCB/WCC, CL150#, RF, SWING, TRIM: AISI 316, STELLITE	BS 1868	VCHS,DN150,CL150,FL,CS,410/ST6	EA	2	$ 941.57	$ 1,883.14	
3	CONCERNTRIC BUTTERFLY VALVE	SIZE:4" BODY : DI, DISC : Aluminum Bronze , STEM : F51 , SEAT : EPDM, CONNECTION : Lug PN16 , OPERATION : HANDLE	API STD 609	VBUL,NPS 4,PN16,LUG,RF,DI,EPDM	EA	3	$ 734.72	$ 2,204.16	HANDLE LENGTH 1950 * 2EA 1650 * 1EA
4	VALVE (BALL)	2" A105/A216 GR WCB/WCC, CL150#, RF, RP, LP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN50,CL150,FL,RB,CS,316/PTFE	EA	4	$ 321.02	$ 1,284.08	
5	VALVE (BALL)	2" A182-F316/A351-CF8M, CL150#, FF, RP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN50,CL150,FL,RB,316,316/PTFE	EA	2	$ 626.69	$ 1,253.38	
6	VALVE (BALL)	2" A182-F316/A351-CF8M, CL150#, FLOATING, FF, RP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN50,CL150,FL,RB,316,316/PTFE	EA	5	$ 626.69	$ 3,133.45	
7	VALVE (BALL)	1.5" A182-F316/A351-CF8M, CL150#, FLOATING, FF, RP, TRIM: AISI 316, PTFE	ISO 17292	VBA,DN40,CL150,FL,RB,316,316/PTFE	EA	5	$ 476.16	$ 2,380.80	
							TOTAL AMOUNT ($)	**$ 16,977.41**	

NOTE

1. Technical
Any item not specified in this quotation shall be in accordance with Manufacturer's (Neway) standard practice.
Painting: Manufacturer's standard coating system (Shell/MESC coating spec compliance to be confirmed).
Pressure test: API 598 or API 6D. Visual inspection of castings: MSS-SP-55 / ASME B16.34. Marking: MSS-SP-25.
NDE not included unless specifically listed in this quotation; available at additional cost if required by MESC SPE.
2. Inspection
Ex-works delivery upon completion of Seller's own in-house inspection.
Third-party (source) inspection cost, if required by Purchaser, to be borne by Buyer.
3. Documentation
Documents included: MTC/Test Report per EN 10204 3.1, API 598/6D test certificates, GA Drawing, IOM Manual, Standard QC Plan.
GA Drawing, Data Sheet & Calculation Sheet available after order confirmation only.
Other documentation available upon request and may incur additional cost.
4. Packing method : Export seaworthy wooden box.

TERMS	
CURRENCY	USD
PROJECT	NIGERIA HI OPF BLOCK PJ
MAKER	NEWAY (CHINA), ZG VALVE (CHINA)
DELIVERY TIME:	EXW 20~24 weeks after PO
DELIVERY TERMS	FOB CHINA SEA PORT
PAYMENT:	T.T (30% in advance / 60% after delivery / 10% approval of Final as-built drawing)



SIGNATURE
CHRISTIAN .E. A./Director

Chrisbeth Integrated
CONCEPT LTD
RC: 672619 | TIN NO: 15227158-0001

No. 8 Chief Gilbert Nworlu Avenue
Rumuokoro, Port Harcourt,
Rivers State, Nigeria.

Tel: +234 916 317 9301

QUOTATION

RC NO: 672619
TIN NO: 15227158-0001

PROCUREMENT OFFICER
DAEWOO E&C NIGERIA LIMITED
MR. AGBARA PRINCE

Quote # Quote-CICL-0026/1016-10
Quote Date: 20/10/2026
MR Number: OPCH1-KP005D-01
Item Description: FLANGE

S/N	ITEMS	DESCRIPTION	MANUFACTURER	UNIT	QTY	UNIT PRICE ($)	AMOUNT ($)
1	FLANGE (WELD NECK)	24" ASTM A105, CL150#, RFWN, SCH 20 BORE	Shanxi Guanjiaying Flange (China)	EA	2	$ 524.77	$ 1,049.54
2	FLANGE (BLIND)	24" ASTM A105, CL150#, RF	Shanxi Guanjiaying Flange (China)	EA	1	$ 874.05	$ 874.05
3	WELDLET	24" x 6" SCH 40, ASTM A105	Samho fitting (korea)	EA	1	$ 153.60	$ 153.60
4	WELDLET	6" x 2" SCH 40, ASTM A105	Samho fitting (korea)	EA	2	$ 11.37	$ 22.74
5	PLUG (THRD)	0.5" ASTM A105, HEX HEAD, CL3000 FS	Samho fitting (korea)	EA	6	$ 1.69	$ 10.14
6	FLANGE (WELD NECK)	6" ASTM A105, CL150#, RFWN, SCH 40 BORE	Shanxi Guanjiaying Flange (China)	EA	12	$ 50.89	$ 610.68
7	FLANGE (LAP JOINT)	4" ASTM A105, CL150#, SCH DR11 BORE	Shanxi Guanjiaying Flange (China)	EA	9	$ 22.95	$ 206.55
8	FLANGE (LAP JOINT)	3" ASTM A105, CL150#, SCH DR11 BORE	Shanxi Guanjiaying Flange (China)	EA	4	$ 19.75	$ 79.00
9	FLANGE (WELD NECK)	2" ASTM A105, CL150#, RFWN, SCH 40 BORE	Shanxi Guanjiaying Flange (China)	EA	3	$ 14.80	$ 44.40
10	FLANGE (WELD NECK)	2" ASTM A105, CL150#, RFWN, SCH 80 BORE	Shanxi Guanjiaying Flange (China)	EA	8	$ 15.45	$ 123.60
11	FLANGE (LAP JOINT)	2" ASTM A105, CL150#, SCH DR11 BORE	Shanxi Guanjiaying Flange (China)	EA	58	$ 12.22	$ 708.76
12	FLANGE (WELD NECK)	2" ASTM A105, CL150#, FFWN, SCH 80 BORE	Shanxi Guanjiaying Flange (China)	EA	2	$ 15.45	$ 30.90
13	FLANGE (BLIND)	2" ASTM A105, CL150#, RF	Shanxi Guanjiaying Flange (China)	EA	3	$ 12.36	$ 37.08
14	FLANGE (BLIND)	1.5" ASTM A105, CL150#, FF	Shanxi Guanjiaying Flange (China)	EA	6	$ 7.85	$ 47.10
15	FLANGE (LAP JOINT)	1.5" ASTM A105, CL150#, SCH DR11 BORE	Shanxi Guanjiaying Flange (China)	EA	6	$ 7.99	$ 47.94
16	Project Extra Cost	Packing, Documents		LOT	1	$ 640.00	$ 640.00
						TOTAL AMOUNT ($)	**$ 4,686.08**


NOTES

CERT : EN10204/3.1.
Packing: about 1500 kilograms flanges in a plywood box/pallet , seaworthy.
Surface: CS--anti-rust oil, SS--Clean

TERMS

CURRENCY	USD
PROJECT	NIGERIA HI OPF BLOCK PJ
DELIVERY TIME:	6~8 weeks After PO
PAYMENT TERM:	T.T (30% in advance / 60% after delivery / 10% approval of Final as-built drawing)
DELIVERY TERMS	FOB CHINA SEA PORT, FOB KOREA SEA PORT





SIGNATURE
CHRISTIAN .E. A./Director

QUOTATION

RC NO: 672619
TIN NO: 15227158-0001

PROCUREMENT OFFICER
DAEWOO E&C NIGERIA LIMITED
MR. AGBARA PRINCE

Quote # Quote-CICL-0026/1016-11
Quote Date: 20/10/2026
MR Number: OPCH1-KP006D-01
Item Description: Gasket

S/N	PL	ITEMS	DESCRIPTION	SIZE	UNIT	QTY	UNIT PRICE ($)	AMOUNT ($)
1		MG 913M 316/316/FG/CS	ASME 16.20; 4.5 MM Thickness AND 3.2 MM THK for inner ring& Outer ring	24" CL150	EA	4	$ 66.59	$ 266.36
2		MG 913M 316/316/FG/CS	ASME 16.20; 4.5 MM Thickness AND 3.2 MM THK for inner ring& Outer ring	6" CL150	EA	18	$ 13.75	$ 247.50
3		MG 913M 316/316/FG/CS	ASME 16.20; 4.5 MM Thickness AND 3.2 MM THK for inner ring& Outer ring	2" CL150	EA	16	$ 3.92	$ 62.72
4		SPCG EPDM - 3.2MM	* Flat EPDM gasket per ASME B16.21 offered; "Ring D" (ring type) not quoted by maker. * RF FACE, HARDNESS 70+/-5 SHORE A	4" CL150	EA	14	$ 2.53	$ 35.42
5		SPCG EPDM - 3.2MM	* Flat EPDM gasket per ASME B16.21 offered; "Ring D" (ring type) not quoted by maker. * RF FACE, HARDNESS 70+/-5 SHORE A	3" CL150	EA	6	$ 1.83	$ 10.98
6		SPCG EPDM - 3.2MM	* Flat EPDM gasket per ASME B16.21 offered; "Ring D" (ring type) not quoted by maker. * RF FACE, HARDNESS 70+/-5 SHORE A	2" CL150	EA	92	$ 1.13	$ 103.96
7		SPCG EPDM - 3.2MM	* Flat EPDM gasket per ASME B16.21 offered; "Ring D" (ring type) not quoted by maker. * RF FACE, HARDNESS 70+/-5 SHORE A	1-1/2" CL150	EA	16	$ 0.78	$ 12.48
8		Packing Charge			LOT	1	$ 384.00	$ 384.00
							TOTAL AMOUNT ($)	**$ 1,123.42**


Chrisbeth Integrated
CONCEPT LTD
RC: 672619 | TIN NO: 15227158-0001

No. 8 Chief Gilbert Nworlu Avenue
Rumuokoro, Port Harcourt,
Rivers State, Nigeria.

Tel: +234 916 317 9301

NOTE
Certification :EN10204-2.1 (Non-Metal), EN10204-3.1 (Metal) 1. Technical: Tolerances per ASME B16.20 (spiral wound) and ASME B16.21 (flat gaskets). Metal properties per ASTM. Sealing element, inner ring and outer ring supplied with minimum weld joints for sizes above 150 mm. 2. Testing: Performance and compressibility tests on prototype basis only, if applicable. 3. Certification: EN10204-2.1 for non-metal gaskets; EN10204-3.1 for metal gaskets / metal parts; EN10204-3.2 for metal gaskets available on request . third-party inspection charges extra (not included), per approved QAP). 4. Clarification: Items 1~3 are offered as 4.5 mm thick spiral wound gasket with 3.2 mm inner/outer rings (MESC 854136.342.1 / .324.1 / .314.1 CL150 basis). Items 4~7 are flat EPDM gaskets (ASME B16.21); ring type (Ring D) is not quoted.

TERMS	
CURRENCY	USD
PROJECT	NIGERIA HI OPF BLOCK PJ
MAKER	Teadit Packing & Gaskets Pvt. Ltd. (india)
DELIVERY TIME:	EXW 4~5 weeks after PO
DELIVERY TERMS	EX-Works Vadodara, India
PAYMENT TERMS	T.T (30% in advance / 60% after delivery / 10% approval of Final as-built drawing)



SIGNATURE
CHRISTIAN .E. A./Director

RC NO: 672619
TIN NO: 15227158-0001

PROCUREMENT OFFICER
DAEWOO E&C NIGERIA LIMITED
MR. AGBARA PRINCE


QUOTATION

Quote # Quote-CICL-0026/1016-12
Quote Date: 20/10/2026
MR Number: OPCH1-KP007D-01
Item Description: Stud Bolt & Nut

S/N	ITEMS	DESCRIPTION	UNIT	QTY	UNIT PRICE ($)	AMOUNT ($)
1	STUD BOLTS with NUTS	STUDBOLT ASTM A193 GR. B7 (ASME B18.31.2) C/W 2 UNITS OF HEAVY HEX NUT ASTM A194 GR. 2H (ASME B18.2.2), NANO GALVANIZED, 1 1/4" - 8UN X 180MM	SET	44	$ 24.50	$ 1,078.00
2	STUD BOLTS with NUTS	STUDBOLT ASTM A193 GR. B7 (ASME B18.31.2) C/W 2 UNITS OF HEAVY HEX NUT ASTM A194 GR. 2H (ASME B18.2.2), NANO GALVANIZED, 1 1/4" - 8UN X 220MM	SET	22	$ 27.48	$ 604.56
3	STUD BOLTS with NUTS	STUDBOLT ASTM A193 GR. B7 (ASME B18.31.2) C/W 2 UNITS OF HEAVY HEX NUT ASTM A194 GR. 2H (ASME B18.2.2), NANO GALVANIZED, 1/2" - 13UNC X 80MM	SET	35	$ 1.84	$ 64.40
4	STUD BOLTS with NUTS	STUDBOLT ASTM A193 GR. B7 (ASME B18.31.2) C/W 2 UNITS OF HEAVY HEX NUT ASTM A194 GR. 2H (ASME B18.2.2), NANO GALVANIZED, 3/4" - 10UNC X 110MM	SET	79	$ 5.67	$ 447.93
5	STUD BOLTS with NUTS	STUDBOLT ASTM A193 GR. B7 (ASME B18.31.2) C/W 2 UNITS OF HEAVY HEX NUT ASTM A194 GR. 2H (ASME B18.2.2), NANO GALVANIZED, 5/8" - 11UNC X 110MM	SET	13	$ 3.64	$ 47.32
6	STUD BOLTS with NUTS	STUDBOLT ASTM A193 GR. B7 (ASME B18.31.2) C/W 2 UNITS OF HEAVY HEX NUT ASTM A194 GR. 2H (ASME B18.2.2), NANO GALVANIZED, 5/8" - 11UNC X 100MM	SET	136	$ 3.47	$ 471.92
7	STUD BOLTS with NUTS	STUDBOLT ASTM A193 GR. B7 (ASME B18.31.2) C/W 2 UNITS OF HEAVY HEX NUT ASTM A194 GR. 2H (ASME B18.2.2), NANO GALVANIZED, 5/8" - 11UNC X 90MM	SET	163	$ 3.29	$ 536.27
					TOTAL AMOUNT ($)	**$ 3,250.40**

NOTES
Certificat : EN10204.3.1 Coating : Acc to MESC SPE 81/009

TERMS	
CURRENCY	USD
PROJECT	NIGERIA HI OPF BLOCK PJ
DELIVERY TIME:	2~3 Months after po
MAKER	SBN Industries Sdn. Bhd. (Malaysia)
DELIVERY TERMS	FOB BUSAN SEA PORT
PAYMENT TERMS	T.T (30% in advance / 60% after delivery / 10% approval of Final as-built drawing)



SIGNATURE
CHRISTIAN .E. A./Director